



June 25, 2022

Glenn D. Illing, P.E.
Professional Engineer 1
NYS Dept. of Health, Monticello District Office
50 North Street, Suite 2
Monticello, New York 12701
(845) 794-2045
email: glenn.illing@health.ny.gov

**RE: Camp FIMFO Catskill
SUN NG KITTATINNY RV LLC
3854 State Route 97
Barryville, NY**

On-site Wastewater Management Design – Flow Confirmation Letter

Mr. Illing:

LaBella Associates has computed the Design Flow Rate for all existing and proposed wastewater treatment systems for this property to be **29,080 GPD**.

As detailed in Table 1, attached, there are 9 existing septic systems with a design flow rate of 6,300 gpd.

The proposed upgrade and improvement project for the project includes the addition of 16 new septic systems with a total design flow rate of 22,780 gpd. Twelve of the systems will support the conversion of existing tent camping sites to sewer sites. The remaining four systems will handle wastewater from the backwash system for the aquatic center; convenience bathrooms at the Adventure Center; snack shop; and 4 proposed washing machines in the maintenance building.

Based on the total design flow rate, it is our understanding that the DOH will be completing the technical review of the proposed septic systems. We further understand that the existing General SPDES Permit from DEC will need to be updated to include the 16 new systems.

If you have any questions or concerns with our approach, or if you require additional information, please let us know.

Respectfully submitted,

LaBella Associates

Jody M. Allen, PE
Senior Civil Engineer
jallen@labellapc.com
607-725-1547

October 26, 2022



TO: Mike Mueller
Chris Chilek
Fancy Parsley
233 Oakford Court
Scranton, PA18503

DATE OF INSPECTION: September 23, 2022

SUBJECT: Kittatinny Campgrounds
Existing Pedestrian Bridge

PURPOSE: Visually inspect existing pedestrian bridge to determine its condition and establish load ratings.

INTRODUCTION:

This report represents the professional opinion of Mr. Vincent A. Griffin, P.E. The field survey was conducted by Vincent A. Griffin, P.E. and Anthony Tompkins. No testing (non-destructive or destructive) or removal of coverings or earth backfill was done unless specifically mentioned in this report. Due care was exercised in the performance of this report, but Mr. Griffin neither makes representation nor guarantees with respect to latent deficiencies or future conditions as part of the inspection or this report.

BRIDGE DESCRIPTION:

The existing pedestrian bridge is a seven foot six inch (7'-6") wide by forty-feet six inch (40'-6"+/-) long single span steel structure with timber deck and bridge rail system that spans over a creek (See photo #1). The existing bridge superstructure consists of two eighteen-inch (18") deep "S-Shaped" steel girders spaced seven feet (7'-0") on center that appear to be embedded into the earth embankments on each end of the bridge. The existing bridge substructure was not visible on either end of the bridge due to the substantial amount of plant overgrowth. Along the span, four (4) eighteen inch (18") deep steel channels laterally brace the existing steel girders. One channel is located three inches in from each end of the bridge with the next channel spaced fifteen feet (15'-0") from the first channel. A three inch (3") deep steel "I" beam is located at mid-width of the bridge, span longitudinally between the transverse steel channels.

At the bridge surface, 3" deep timber decking of varying widths (3"x6" to 3"x12") span transversely across the width of the bridge supported by the two steel girders and the 3" deep "I" beam at midspan. The timber decking extends approximately one inch (1") beyond the steel girders flange on each side of the bridge.

A three-rail bridge rail system consisting of three (3) 1"x6" rails on 4"x4" posts spaced 5'-0" on center is located along the edge of deck on both sides of the bridge. A continuous 1x6 wood plate runs over the top of each post along the bridge length. The

overall height of the pedestrian bridge rail system from top of bridge deck surface to top of continuous top plate is forty-one inches (41").

Items observed during our on-site visual inspection are noted in our photos and recommendations that follow.



PHOTO #1 –

Deteriorated timber deck on north end of bridge

Three-rail pedestrian bridge rail system



PHOTO #2 – Steel beam embedded in earth embankment

Rust prevalent on steel beam surface.




PHOTO #3 –

Deteriorated timber deck on south end of bridge




PHOTO #4 –

Deteriorated timber deck above the first transverse steel beam on the north end of bridge




PHOTO #5 –

Deteriorated timber deck above the first transverse steel beam on the south end of bridge




PHOTO #6 –

Underside of deteriorated timber deck between 1st & 2nd channel on south end of bridge

No end diaphragm present between end of bridge and adjacent finished grade as seen by the light penetrating through



PHOTO #7 – Underside of deteriorated timber deck between 1st & 2nd channel on north end of bridge

No end diaphragm present between end of bridge and adjacent finished grade as seen by the light penetrating through

Beams embedded in soil

Significant rusting on all steel framing



PHOTO #8 – Beams embedded in soil on northwest end of bridge

No end diaphragm separating bridge structure from soil

Deteriorated deck

EVALUATION/RECOMMENDATIONS:

1. In general, the existing pedestrian bridge cannot be load rated based on the deteriorated condition of the existing timber deck. Therefore we recommend removing all existing timber decking and replace with minimum PT 4x8 decking, to span seven feet (7'-0") between existing steel fascia beams.

NEW PT 4"x8" TIMBER DECK LOAD RATING:

The new PT 4x8 deck would be able to support a maximum concentrated wheel load of 575# or a total maximum golf cart weight (cart+people+cargo) of 2300# for a deck span of 7'-0". This analysis is based on a single plank supporting two concentrated wheel loads with a front wheelbase of 33" and a rear wheelbase of 38" for a typical golf cart.

There is surface rusting visible on the steel fascia beams but it is not significant and does not reduce the load carrying capacity of the structure.

EXISTING S18x70 STEEL FASCIA BEAM LOAD RATING:

The existing steel fascia beams on each side of the bridge can support a maximum concentrated wheel load of 7.75 Kips or a total maximum vehicle weight (cart+people+cargo) of 31Kips for a deck span of 7'-0".

Our analysis of the existing steel pedestrian bridge indicates that it should be rated for a maximum vehicle weight of **1.15 tons (2,300 pounds)**. This load rating is controlled by the capacity of the proposed new PT wood decking. If additional beams are added to reduce the new deck span, this load rating could be increased.


2. *The existing pedestrian bridge rail system does not comply with AASHTO requirements for pedestrian bridges. The following items do not comply:*
 - a. *The minimum overall height of a pedestrian bridge rail system is 42" above the bridge surface. As constructed, the current bridge rail system is one inch (1") too short.*
 - b. *The maximum clear opening between rails shall be such that a 6" sphere cannot pass through. As constructed, the clear space between rails is greater than six inches (6").*
 - c. *The existing 1"x6" horizontal rails do not have the capacity to resist the code minimum 50 plf live load force applied transversely and vertically acting simultaneously in addition to a 200# concentrated force. Each longitudinal rail is required to meet this design load requirement. To meet this requirement, we recommend removing the 1x6 rails and replace with PT 3x6 or PT 2x8 rails minimum, spacing to comply with item (b) above.*
 - d. *A safety toe rail or curb shall be provided. Currently none exist.*

October 26, 2022

We recommend replacing the existing bridge rail system with an OSHA compliant rail system.

This concludes my report. Please contact our office should you wish to discuss our findings.

Sincerely,

A handwritten signature in black ink, appearing to read "Vincent A. Griffin". The signature is fluid and cursive, with a large initial "V" and "G".

Vincent A. Griffin, P.E.
E. D. Pons Associates, P.C.

Table 1.0 - Septic System Design Table

Site #	Area Name	Outfall #	Total Sites Requiring Sewer	Design Flow Rate @ 100 gpd/site	Design Flow Rate	Required LF of Ejlens (1)	# of 60' Long Ejlens Trenches Required	Type of System	Notes
EXISTING (2)									
	Bathroom East	001			1,000			Seepage Pits	Existing Permitted by DEC
	Bathroom	006			1,200			Seepage Pits	Existing Permitted by DEC
	900's	008	23		2,300			Absorption Beds	Existing Permitted by DEC
	Unknown	002			600			Seepage Pits	Existing Not permitted
	Unknown	003			200			Absorption Beds	Existing Not permitted
	Unknown	004			100			Seepage Pits	Existing Not permitted
	Unknown	005			100			Absorption Beds	Existing Not permitted
	Unknown	007			400			Seepage Pits	Existing Not permitted
	River House	009			400			Seepage Pits	Existing Not permitted
					6,300				
PROPOSED									
100S	Main Camp	010	26	2,600		619	11	Ejlens Trenches	
200S	Beaver Run (A)	011	17	1,700		405	7	Ejlens Trenches	
	Beaver Run (B)	012	8	800		190	4	Ejlens Trenches	
300S	Hemlock Point	013	25	2,500		595	10	Ejlens Trenches	
400S	Trout Terrace & Secluded Summit	014	33	3,300		786	13	SHALLOW Ejlens Trenches	
500S	Chad's Bluff	015	8	800		190	4	Ejlens Trenches	
600S	Woodlands SS1	016	67	6,700		1595	27	Ejlens Trenches	
	Woodlands SS2	017							Provide 4 systems with 7 rows per system = 28 Total
	Woodlands SS3	018							
	Woodlands SS4	019							
900S	Luke's Landing (A)	Existing Outfall 008	23	Outfall #008					
	Luke's Landing (B)	020	4	400		95	2	Ejlens Trenches	
	Mountainside	021	22	2,200		524	9	SHALLOW Ejlens Trenches	
	Aquatic Center Backwash System	022			400 (3)	95	2	Ejlens Trenches	
	Adventure Center	023			500 (4)	120	2	Ejlens Trenches	
	Food and Beverage	024			400 (5)	95	2	Ejlens Trenches	
	Maintenance and Laundry	025			480 (6)	114	2	Ejlens Trenches	
	Total by Type		230	21,000	1,780	5,423	96	rows x 60' = 5,760	
	Total of All Systems	25 (7)		29,080	GPD				

(1) Based on 20 min perc rate, 0.7 GPD/SF. All perc rates were less than 20 minutes.

(2) Existing on-site systems per DEC SPDES Permit

(3) This includes 400 gallons per month for the Defender Filters for pool and 2,400 gallons per week for spa. Wastewater will be held and released daily.

(4) Check in convenience restroom and employee restroom. All visitors have access to bathroom facilities in existing bathhouses and/or camping sites.

(5) Food beverage area is primarily a snack shop with limited food prep and dishwashing, employee bathroom

(6) Water used based on 4 high efficiency washing machines, 8 loads/machine/day, 15 gallons/load = 480 gallons. Average water use for a HE machine is 13-15 gallons/cycle, average wash cycle is 60-85 minutes

(7) 9 of the systems are existing, 16 of the systems are proposed